

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-22916-00-00  
Spot: NESESW Sec/Twnshp/Rge: 17-8S-17W  
990 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: LESLIE WELLS Well #: 4  
County: ROOKS Total Vertical Depth: 3415 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3415		150 SX
SURF	8.625	213		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2013 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO. Phone: (785) 259-1928

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
Production perforations: 2995' - 3388'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/19/2013 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 790', 1300' and 1800'.  
Ran tubing to 2850' and pumped 125 sx cement w/300 # hulls.  
Pulled tubing to 1900' and pumped 125 sx cement w/300 # hulls.  
Pulled tubing to 950' and pumped 85 sx cement w/100 # hulls to circulate cement to surface.  
Pulled all tubing. Topped off 5 1/2" casing w/105 sx cement.  
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 5 sx cement w/200psi shut in pressure.  
GPS: 39.35293 N -099.24272W

Perfs:

Top	Bot	Thru	Comments
3360	3388		

Remarks: ALLIED TICKET # 54870

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

CM

✓ 10/25/13

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

SEP 25 2013

OCT 09 2013

CONSERVATION DIVISION  
WICHITA, KS