

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20342-00-00  
Spot: SWSESW Sec/Twnshp/Rge: 17-8S-17W  
330 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: LESLIE WELLS 1-V Well #: 1-V  
County: ROOKS Total Vertical Depth: 3429 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3429		175 SX
SURF	8.625	245		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/19/2013 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO Phone: (785) 259-1928

Proposed Plugging Method: Ordered 370sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Production perforations: 3110' - 3309'  
Squeezed 740' with 200 sx cement and 2619' w/150 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/19/2013 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2850' and pumped 125 sx cement w/200 # hulls.  
Pulled tubing to 1900' and pumped 125 sx cement w/200 # hulls.  
Pulled tubing to 950' and pumped 100 sx cement w/100 # hulls to circulate cement to surface.  
Pulled all tubing and topped off 5 1/2" casing with 10 sx cement.  
Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi

Perfs:

Top	Bot	Thru	Comments
3307	3309		
3285	3289		
3266	3270		

Remarks: ALLIED TICKET # 54869

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*

(TECHNICIAN)

*CM*

*10/25/13*

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

SEP 25 2013

OCT 09 2013

CONSERVATION DIVISION  
WICHITA, KS