

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40435-00-00
Spot: NWNEENE Sec/Twnshp/Rge: 34-34S-10E
5092 feet from S Section Line, 583 feet from E Section Line
Lease Name: KEENAN Well #: 16
County: CHAUTAUQUA Total Vertical Depth: 1433 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.5	1250		0 SX
SURF	10.625	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2013 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 800' and 500'. Run 1" back in and spot 50' plug of cement at 800'. Pull up to 500' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 10/01/2013 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1300' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" in to 900' and spotted 15 sack plug. Pulled up to 550' and circulated cement to surface inside and outside of casing. Pulled 1" and topped well off. A total of 117 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 14 2013
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
OCT 08 2013
KCC Chanute Dist. #3


DS

Remarks:

Plugged through: TBG

District: 03

Signed


10/25/13

(TECHNICIAN)