

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-20939-00-00  
Spot: NESWSWNW Sec/Twnshp/Rge: 19-16S-19W  
3005 feet from S Section Line, 4708 feet from E Section Line  
Lease Name: HAZELHORST Well #: 1  
County: RUSH Total Vertical Depth: 3908 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3907	0	WITH 200 SX CMT
SURF	8.625	316		WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/23/2013 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (785) 483-1683

Proposed Plugging Method: PUMP DOWN 4 1/2" WITH 100# HULLS-25 SX CMT-GEL SPACER TO 1350'. CMT TO SURFACE. PRESSURE TEST 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/24/2013 1:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report: \_\_\_\_\_ Perfs: \_\_\_\_\_

\*\*DID ALTERNATE II IN 1985' BY PERFORATING @ 1342' & PUMPING 550 SX CMT. PERFORATED @ 450' & PUMPED 150 SX CMT. PERFORATED @ 317' & PUMPED 100 SX CMT. CIRCULATING TO SURFACE.\*\* PUMPED DOWN 4 1/2" CASING WITH 100# HULLS MIXED IN 25 SX CMT FOLLOWED BY 25 SX GEL - 115 SX CMT. CASING WAS ON A VACUUM. SHUT DOWN FOR 30 MINUTES. CMT TOP @ 630'. PUMPED 20 SX CMT & CMT TOP WAS AT 480'. VISUALLY CHECKED 8 5/8" X 4 1/2" ANNULUS & IT WAS FULL OF CMT. 9/24/13: PUMPED 70 SX CMT TO TOP OFF THE WELL.

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.  
Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
OCT -7 2013  
KCC DODGE CITY

10/25/13

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 10 2013

CONSERVATION DIVISION  
WICHITA, KS

*Handwritten signature*