

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21349-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 19-16S-19W
4947 feet from S Section Line, 1015 feet from E Section Line
Lease Name: OELKERS Well #: 1
County: RUSH Total Vertical Depth: 3900 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3897	0	WITH 200 SX CMT
SURF	8.625	570		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2013 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL Phone: (214) 219-8883

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & GEL TO ANHYDRITE. PULL TBG TO ANHYDRITE & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & TRY TO PUMP 100 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2013 12:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

**HOLE SQUEEZED @ 2640' WITH 20 SX CMT. HOLES SQUEEZED FROM 611' TO 1268' WITH 250 SX CMT. HOLES SQUEEZED FROM 2016' TO 2047' WITH 30 SX CMT. **RUN TBG TO 3419' & PUMP 10 SX GEL & 300# HULLS, THEN 50 SX CMT WITH 200# HULLS. PULL TBG TO 1271' & PUMP 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 16 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
10/25/13 (TECHNICIAN)

RECEIVED
OCT 14 2013
KCC DODGE CITY

AMW