

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21107-00-01  
Spot: W2NWNWSW Sec/Twnshp/Rge: 34-17S-25W  
2310 feet from S Section Line, 4963 feet from E Section Line  
Lease Name: PALOMINO REED Well #: W-1  
County: NESS Total Vertical Depth: 4378 feet

Operator License No.: 3925  
Op Name: MISHLER, ROBERT DBA MISHLER OIL  
Address: 400 W. 1ST ST  
RANSOM, KS 67572

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1650		WITH 300 SX CMT
PROD	5.5	4293	0	WITH 175 SX CMT
SURF	8.625	338		WITH 300 SX CMT

Well Type: EOR UIC Docket No: E18583.1 Date/Time to Plug: 09/10/2013 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO 3200' & PUMP 10 SX GEL & 50 SX CMT. PULL TBG TO 1680' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP CMT UNTIL IT PRESSURES TO 500#.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/10/2013 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3150' & PUMPED 10 SX GEL THEN 50 SX CMT WITH 100# HULLS. PULLED TBG TO 1662' & PUMPED 165 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4293	4373		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)  
cc to UK 9/29/13

RECEIVED  
SEP 16 2013  
KCC DODGE CITY

KCC WICHITA Form CP-2/3

SEP 18 2013

RECEIVED

*RMJ*