

1 040764

6-18

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-01,033-0001
SW NE NE, SEC. 2, T 31 S, R 14 W/EX
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399
Operator: Farrar Pump & Supply Co. Inc
Name & Address P.O. Box 209
Medicine Lodge, KS 67104

Lease Name Skinner Well # 2
County Barber
Well Total Depth 4621 150.18 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 900

Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated never produced

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:45 a.m. Day: 18 Month: 6 Year: 19 93

Plugging proposal received from Mike Farrar
(company name) Farrar Pump & Supply Co., Inc. (phone) B16-886-3763
were: 5 1/2" at 4473' w/150 sx cement, Open hole 4403-4621'

1st plug sand back to 4367' and dump 5 sx cement on top of sand bridge through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 12 p.m. Day: 18 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4367' and dumped 5 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls and 100 sx cement.
Maximum pressure 1000 psi and shut in 650 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2330.75' of 5 1/2" casing.
additional description is necessary, use BACK of this form.

INVOICED

I (did / did not) observe this plugging.

DATE 7-9-93
WV. NO. 38084

Signed Stephen J. Pfeifer
(TECHNICIAN)
RECEIVED
STATE CORPORATION COMMISSION
6-23-93
JUN 23 1993
CONSERVATION DIVISION
Wichita, Kansas