

1 040808

11-24

007-21,575-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
NW NE, SEC. 10, T 31 S, R 14 W/E  
660 feet from ~~NX~~ section line  
2098 feet from E section line  
Lease Name Nittler Well # 10-1  
County Barber  
Well Total Depth 3120 101.40 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 898

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653  
Operator: Petroleum Technologies Inc.  
Name & Address: 500 Nichols Rd., Ste. 407  
Kansas City, MO 64112

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 24 Month: 11 Year: 1993

Plugging proposal received from Richard McIntyre  
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3119' w/150 sx cement, PBSD 3070', Perfs at 3048-3050'  
1st plug sand back to 3000' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 10 sx gel and 50 sx cement at 920',  
3rd plug pump 40 sx cement at 450',  
4th plug pump 10 sx cement at 40'

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11 a.m. Day: 24 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 3000' and dumped 5 sx cement on top of sand  
bridge through bailer,  
2nd plug loaded hole with fresh water from 920' to surface through 5 1/2" casing and spotted  
through 5 1/2" casing 10 sx gel and 50 sx cement at 920',  
3rd plug spotted 5 sx gel and 40 sx cement at 450',  
4th plug spotted 10 sx cement at 40'.

RECEIVED  
STATE CORPORATION COMMISSION  
12-1-93  
DEC 01 1993  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1907' of 5 1/2" casing.  
(Additional description is necessary, use BACK of this form.)

INVOICE  
I (did / ~~XXXXXX~~) observe this plugging.  
DATE: 12-8-93  
WV. No. 39421

Signed Stephen J. Pfeifer (TECHNICIAN)