

1 070034

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4285

Operator: Craig/Stephenson Corporation  
Name & Address P. O. Box 2646  
Ponca City, OK 74602

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Eagle Drilling, Inc. License Number 5380

Address P. O. Box 8609, Wichita, KS 67208

Company to plug at: Hour: 7:00 pm Day: 19 Month: October Year: 19 85

Plugging proposal received from Butch Steinert

(company name) Eagle (phone) 316-682-5513

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1718'  
Anhydrite 1620'

1st plug at 1650' with 50 sx cement

2nd plug at 335' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:30 pm Day: 19 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement, 2nd plug at 335' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement. 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1985

10-28-85  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(copy to be observed) observe this plugging.

OCT 29 1985

DATE 10/29

INV. NO. 10771

10-19

DEC 13 1985

Signed Dan Goodrow  
JAN 16 1986

(TECHNICIAN)

P.a.l.

API NUMBER 15- 00722,092-0000  
NE NW NE, SEC. 6, T. 31 S, R. 14 W  
4950 feet from S section line  
1600 feet from E section line  
Lease Name Bibb Well # 2  
County Barber 126.75  
Well Total Depth 3900 Douglas feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 305

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: October 14, 1985  
month day year 2:36

API Number is: 007-22092-0000

OPERATOR: License # 4285  
Name: Craig/Stephenson Corporation  
Address: Box 2646  
City/State/Zip: Ponca City, OK 74602  
Contact Person: Jeff Wolfe  
Phone: 405-762-9062

NE NW NE Sec 6 Twp 31 S. Rge 14  East  
(location)  West  
4950 Ft North from Southeast Corner of Section  
1600 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5380  
Name: Eagle Drilling, Inc.  
City/State: Wichita, KS 67208

Nearest lease or unit boundary line 330 feet.  
County: Barber  
Lease Name: Bibb Well# 2  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 100 feet  
Lowest usable water formation Permian  
Depth to Bottom of usable water 200 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 300 feet  
Conductor pipe if any required None feet  
Ground surface elevation 1718 feet MSI  
This Authorization Expires 4-14-86  
Approved By 10-14-85

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 3900 feet  
Projected Formation at TD Douglas  
Expected Producing Formations Douglas

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.  
Date 10-14-85 Signature of Operator or Agent Robert J. Eup Title Pres., Eagle Drilling, Inc.  
Form C-1 4/84

TD - 3900'  
Any - 1620'

move-in 10-13-85  
spud 10-13-85  
850' at 305'

PUSHER	Batch Steiner	FORMATION	
TD	3900'	SURFACE PIPE	8 3/4" @ 305'
ANHYDRITE	1620'	ELEVATION	1718'
STARTING TIME & DATE		COMPLETION TIME & DATE	10-14-85 9:30 PM
1st PLUG @	1650' FT. W/ 50	SX	
2nd PLUG @	335' FT. W/ 40	SX	
3rd PLUG @	40' FT. W/ 10	SX	
4th PLUG @		SX	
RAT HOLE CIRCULATED W/	15	SX	
MOUSE HOLE CIRCULATED W/	10	SX	
WATER WELL PLUGGED W/		SX	
CEMENT COMPANY	DJ Titan		
TECHNICIAN	Geo Ren		
		60/40 pot. 6% ga	
		Called 3:55 PM 10-18-85	
		will be approx 7:00 PM 10-18-85	
STATE CORPORATION COMMISSION			
OCT 28 1985			
10-28-85			
CONSERVATION DIVISION			
Kansas			