

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007 -21,832-0000

SW SW NE, Sec. 4, T 31 S, R 14 W/E  
2310 feet from N/SX section line  
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Nittler Well # 1

Operator: W. L. Kirkman, Inc.  
Name & P. O. Box 18611  
Address Wichita, KS 67218

County Barber

Well Total Depth 4685 feet 152.26

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 933

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 1:00 pm Day: 11 Month: June Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Larry Harris

(company name) Aldebaran (phone) 316-672-3473

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4646' with 40 sx cement

2nd plug at 983' with 50 sx cement

3rd plug at 495' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement,

6th plug to circulate rat hole with 15 sx cement. 7th plug to circulate mouse hole

with 10 sx cement

Signed *Glyde Wiley*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:45 pm Day: 11 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4646' with 40 sx cement, 2nd plug at 983'

with 50 sx cement, 3rd plug at 495' with 50 sx cement, 4th & 5th plugs - solid

bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to

circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with

10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

JUN 14 1984  
6-14-84  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I ( / did not) observe this plugging.

INVOICED

DATE 6-18-84

INV. NO. 2064

6-11

Signed *Glyde Wiley*  
(TECHNICIAN)