

1 040349

11-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,023-0000
100' W of
E/2 SE SE SEC. 4, T 31 S, R 14 W/E

660 feet from S section line
430 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9697

Lease Name Nittler Well # 4-1

Operator: Southwest Operating, Inc.
Name & Address C/O Cheyenne Oil Properties
107 N. 4th, #209
Royalty Bldg.
Ponca City, Ok 74601

County Barber 150.90
Well Total Depth 4643 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 870

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 7 Month: 11 Year: 19 89

Plugging proposal received from Kirby Lillard

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4614' PBD 4490' Perfs at 4380-82' Elevation 1680' GL

1st plug pump 25 sx cement to 4200'

2nd plug pump 50 sx cement at 900'

3rd plug pump 25 sx cement at 450'

4th plug pump 10 sx cement at 40'

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 7 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped bottoms with 25 sx cement, bottom plug displaced with drilling mud to 4200'. Spotted plugs through 5 1/2" casing:

2nd plug at 900' with 50 sx cement,

3rd plug at 450' with 25 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1989
11-14-89
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 3236' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. P... (TECHNICIAN) RAVZ

DATE 11-17-89

INV. NO. 26494 FEB 09 1990