

1 010108

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 SW NE, SEC. 3, T 31 S, R 14 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,866-0000

2970 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Mills "G" Well # 1

Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

County Barber 126.43

Well Total Depth 3890 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 314

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor TXO Production Corporation License Number 5171

Address 155 North Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 10:10 am Day: 14 Month: March Year: 19 86

Plugging proposal received from Jerry Collins

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 3195' PBD 3050' Perfs at 3098-3102'; 2994-98'; 2812-14'

1st plug set CIBP at 2950'

2nd plug pump 1 sack hulls, 35 sx cement, 6 sx gel, and 75 sx cement

3rd plug pump 100 sx cement down annulus

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:55 am Day: 14 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2950', 2nd plug squeezed well with 1 sack hulls, 35 sx cement, 6 sx gel, released 4 1/2" rubber plug and pumped 65 sx cement, 3rd plug pumped 100 sx cement down backside (maximum pressure 0 and shut in pressure 0)

Maximum pressure 1000 psi and shut in 500 psi

Remarks: No recovery. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 20 1986

INV. NO. 13040

3-14

observe this plugging.
STATE CORPORATION COMMISSION
MAR 20 1986
3-20-86
CONSERVATION DIVISION
Wichita, Kansas

Signed  (TECHNICIAN)