

1 040744

3-17

22 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,537-0000

W/2 SW SE, SEC. 3, T. 31 S, R. 14 W&X

700 feet from S section line  
2245 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653

Lease Name Nittler Well # 3-3

Operator: Petroleum Technologies, Inc.

County Barber 101.72

Name & Address 500 Nichols Rd., Ste. 407

Well Total Depth 3130 feet

Kansas City, MO 64112

Conductor Pipe: Size 16 feet 54

Surface Casing: Size 8 5/8 feet 858

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 4 p.m. Day: 17 Month: 3 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 3128' w/100 sx cement, PBSD 3110', Perfs at 3073-75'

1st plug sand back to 3020' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 17 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3020' and dumped 5 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 ~~50~~ 100 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

MAR 24 1993

3-24-93 CONSERVATION DIVISION WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 3-25-93

WV. NO. 37509

Signed Stephen Pfeifer (TECHNICIAN)