

To: 1040746
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-16

API NUMBER 15-007-21,230-0000 25 R

C SW SW, SEC. 3, T 31 S, R 14 W/E
660 feet from S section line
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8653
Operator: Petroleum Technologies, Inc.
Name & Address: 500 Nichols Rd., Ste. 407
Kansas City, MO 64112

Lease Name Nittler Well # 1
County Barber
Well Total Depth 4650 151.12 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1004

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:15 a.m. Day: 16 Month: 3 Year: 19 93

Plugging proposal received from Jeff Sletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4646' w/150 sx cement, BBTD at 4470', Perfs at 4598-4602', CIBP at 4590,
Perfs at 4523-25', CIBP at 4470'

1st plug set CIBP at 4470',
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 100 sx cement.

RECEIVED

KANSAS CORPORATION COMMISSION

MAR 24 1993 3-24-93 Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:15 a.m. Day: 16 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4470' (no cement on top of CIBP because they
couldn't get the bailer through the pipe-something was floating in the hole),

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did) ~~XXXXXX~~ observe this plugging.

DATE 3-25-93

INV. NO. 37512

Signed Stephen J. Pfeifer (TECHNICIAN)