

To: 1 052214 /-11
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-119-20,990-00-00
App. 12' S & 20' W of
NE NE SE, SEC. 3, T 34 S, R 29 W/R

TECHNICIAN'S PLUGGING REPORT
Operator License # 5003
Operator: McCoy Petroleum Corporation
Name & Address: 3017 N. Cypress St.
Wichita, KS 67226-4003

2298 feet from S section line
350 feet from E section line
Lease Name Hissom "A" Well # 1-3.
County Meade 176.48
Well Total Depth 5430 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1448

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Sweetman Drilling, Inc. License Number 5658

Address 3017 N. Cypress St., Wichita, KS 67226-4003

Company to plug at: Hour: 3 p.m. Day: 10 Month: 1 Year: 19 98

Plugging proposal received from Eugene Saloga

(company name) Sweetman Drilling, Inc. (phone) 316-636-2737

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1440'

1st plug at 1470' with 50 sx cement, 2nd plug at 700' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3 a.m. Day: 11 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 1470' with 50 sx cement,

2nd plug at 700' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 9 3 1998

1-13-98
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

Additional description is necessary, use BACK of this form.)

I (xxx / did not) observe this plugging.

DATE 1-14-98

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 49933

EFFECTIVE DATE: 12-28-97

State of Kansas
119-20, 990

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SG#1 X YES No

NOTICE OF INTENTION TO DRILL
Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date: December 29 1997

Spot Apprx: 12S & 20W of

NE NE SE sec 3 Twp 34S Rng 29W East

OPERATOR: License # 5003
McCoy Petroleum Corporation

Name: 3017 N. Cypress Street
Address: Wichita KS 67226-4003

City/State/Zip: Brent B. Reinhardt
Contact Person: (316) 636-2737

Phone: (316) 636-2737

CONTRACTOR: License # 5658
Sweetman Drilling, Inc.

Name: Sweetman Drilling, Inc.

Well Drilled For: Well Class: Type Equipment:

X OIL Enh Rec Infield X Mud Rotary
X Gas Storage Pool Ext. Air Rotary
OWMO Disposal Wildcat Cable
Seismic; # of Holes Other
Other

If OWMO: old well information as follows:

Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth Bottom Hole Location

Exp. 6/23/98

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

Permit to be applied for by Drilling Contractor.
Will Cores Be Taken? yes X no
If yes, proposed zone: 620' Alt. I Req.

Formation at Total Depth: Mississippian
Water source for Drilling Operations: X well farm pond other

Length of Conductor Pipe required: 5800'
Projected Total Depth: None

Length of Surface Pipe Planned to be set: 1500+/
Surface Pipe by Alternate: X 1 2

Depth to bottom of fresh water: 360'
Depth to bottom of usable water: 600'

Public water supply well within one mile: yes X no
Water well within one-quarter mile: yes X no

Ground Surface Elevation: 2492' GEL feet NSL
Nearest lease or unit boundary: KC, Morrow, Miss 350'

Target Formation(s): Is this a Prorated/Spaced Field? yes X no
Field Name: Mohler well # 1-3

Lease Name: HISSOM "A"
County: Meade

IS SECTION REGULAR X IRRREGULAR?
feet from South / North line of Section
feet from East / West line of Section

Spot Apprx: 12S & 20W of

Pusher Suzer Saloger
SPUD DATE 1-3-98 INIT. SU

LENGTH SURFACE PLANNED 1448'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 1448 CONDUCTOR
ANHYDRITE T- 1440 B- ELEVATION

TD 5430 FORMATION

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1470' Ft. W/ 50 SX

1/2 Base Anyh. @ 200' Ft. W/ 40 SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ Ft. W/ SX

40' Plug @ 40' Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN R. L DATE 1-9-98

TYPE OF CEMENT 60/40/ Poz 6%

STARTING TIME 3:00 (AM/PM) DATE 1-10-98

COMPLETION TIME 3:00 (AM/PM) DATE 1-11-98

CEMENT COMPANY Haliburton

RECEIVED
STATION