

5-18-88 15:35:30246-0000

API NUMBER 15-Drill Completion Date 7/18/66

C NW NW, SEC. 25, T 19 S, R 22 W/E

4620 feet from S section line

4620 feet from E section line

Lease Name Borger Well # 4

County Ness 143.10

Well Total Depth 4403 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 430

1 070553  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Operator: Kaiser-Francis Oil Company

Name & Address P.O. Box 21468

Tulsa, OK 74121-1468

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 18 Month: 5 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4394' PBD 4397' Open hole

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2 p.m. Day: 18 Month: 5 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5' sx cement on top of sand through bailer,

2nd plug pumped 400 lbs. hulls, 10 sx gel, 60 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement down 8 5/8"

Maximum pressure 350 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2030' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
5-23-88  
MAY 25 1988

CONSERVATION DIVISION  
WICHITA, KANSAS

INVOICED  
observe this plugging.

DATE 5-25-88

INV. NO. 20872

Signed Dan Jordan  
(TECHNICIAN)