

1 070883

11-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-135-23,399-0000
150' N of
C. SW NW, SEC. 25, T. 19 S, R. 22 W/E
3450 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8996
Operator: Mid Continent Resources, Inc.
Name & Address P.O. Box 399
Garden City, KS 67846

Lease Name Borger Well # 1
County Ness 145.27
Well Total Depth 4470 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mid Continent Resources, Inc. License Number 8996
Address P.O. Box 399, Garden City, KS 67846

Company to plug at: Hour: 11:30 a.m. Day: 30 Month: 11 Year: 19 90
Plugging proposal received from Scott Corsair

(company name) Mid Continent Resources, Inc. (phone) 316-275-9231
were: 5 1/2" at 4467' w/135 sx cement, PBTD 4420', Perfs at 4380-88', 2-staged 1476-0' w/ 250 sx cement
1st plug pump 50 sx 60/40 Pozmix 2% gel 2% c-322 and 300 lbs. hulls in first part of
195 sx Econolight cement down 5 1/2".

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:25 p. Day: 30 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx 60/40 Pozmix 2% gel 2% c-322 and 300 lbs. hulls in first part of 195 sx Econolight down 5 1/2".

Maximum pressure 1000 psi and shut in 750 psi.
Cement 3' from surface on backside.

DEC 6 1990
12-10-90
CONSERVATION DIVISION
Wichita Kansas

Remarks: Cemented by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-10-90

Signed Dan Goodrow
(TECHNICIAN)

WV. No. 30203

MAR 07 1991

11-30



ACOUSTIC CEMENT BOND LOG

BOND LOG

COMP. MID CONTINENT RESOURCES.	WELL BORGER NO. 1	FIELD SCHABEN	COUNTY NESS	ST. KANSAS	COMPANY MID CONTINENT RESOURCES, INC.						
					WELL BORGER NO. 1		15-135-23399-0000				
					FIELD SCHABEN						
					COUNTY NESS		STATE KANSAS				
API NO. 15-135-23,399		LOCATION 150 FT. N. OF C - SW - NW		OTHER SERVICES		NONE					
SEC. 25		TWP. 19S		RGE. 22W							
PERMANENT DATUM		GROUND LEVEL		ELEV. 2272		ELEV.: K.B. 2277					
LOG MEASURED FROM		KELLY BUSHING		5 FT. ABOVE PERM. DATUM		D.F. 2274					
DRILLING MEASURED FROM		KELLY BUSHING				G.L. 2272					
DATE & TIME LOGGED		12/11/89 1:30 PM		TYPE OF FLUID IN HOLE		WATER					
RUN NO.		ONE		DENSITY OF FLUID		NA					
DEPTH - DRILLER		NA		FLUID LEVEL		FULL					
DEPTH - LOGGER		4420		CEMENT TOP EST. - LOGGED		3870 / 3940					
TIME LOGGED INTERVAL		4409		EQUIPMENT / LOCATION		51539 BT. BEND					
TOP LOGGED INTERVAL		3600		RECORDED BY		MR. J. GILZINGER					
MAX TEMP. DEGREE		132		WITNESSED BY		MR. S. CORSAIR					
CEMENTING DATA		PRODUCTION STRING		PROTECTION STRING		PRODUCTION STRING					
DATE/TIME CEMENTED						LINER					
PRIMARY/SQUEEZE		PRIMARY				VISION					
EXPECTED											
COMP. STRENGTH						OCT 15 1990					
CEMENT VOLUME		SEE REMARKS				CONSERVATION DIVISION					
CEMENT TYPE/WEIGHT						Wichita, Kansas					
FORMULATION											
MUD TYPE/MUD WEIGHT		CHEM 9.10									
RUN NO.		BOREHOLE RECORD				CASING AND TUBING RECORD					
		BIT		FROM TO		SIZE		WGT.		FROM TO	
ONE		12 1/4"		0 270		8 5/8 "		24.0		0 270	
TWO		7 7/8"		270 4470		5 1/2"		11.5		0 4459	