

4-18
API NUMBER 15-135-23,289-0000

1 070659
To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW SE, SEC. 22, T 19 S, R 22 W/E
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3536
Operator: Ramco Energy Corporation
Name & Address P.O. Box 340
Great Bend, KS 67530

Lease Name Rahm Well # 1
County Ness 145.28
Well Total Depth 4470 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 12 Month: 4 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4452' PBD 4418' Perfs at 4356-78'
1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 12 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of
sand through bailer.

2nd plug pumped 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 650 psi and shut in 300 psi.

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1989
4-19-89
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2996' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(did / ~~not~~ observe this plugging.)
INVOICED

Signed Dan Goodwin
(TECHNICIAN)

DATE 4-24-89

INV. NO. 24477