

1 050247

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-21,179-10001  
SE/2 SE, SEC. 15, T 19 S, R 22 W/E

660 feet from ~~W/S~~ section line  
660 feet from ~~W/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5464

Lease Name Schwindt Well # 1

Operator: T & D Oil Company

County Ness

Name & Address Box 278

Well Total Depth 4423 143.75 feet

Victoria, KS 67671

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 548

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 206, Genesco, KS 67444

Company to plug at: Hour: 9:00 am Day: 12 Month: June Year: 19 84

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6467

were: 5 1/2 set at 4423' Perfs 4326-4360

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:15 am Day: 12 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4423' Perfs 4326-4360'

1st plug sanded back to 4300' and dumped 5 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pumped an additional 150 sx cement.

Maximum pressure 900psi and shut in pressure 200 psi.

Remarks: They recovered 2624' of 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun.  
(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED  
STATE CORPORATION COMMISSION Plugging.

DATE 6-25-84 JUN 14 1984

INV. NO. 2128 6-14-84  
6-12 CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lacey  
(TECHNICIAN)