

1090373

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,880 - 6000SE SE SW, SEC. 2, T 20 S, R 22 W X330 feet from S section line2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430Lease Name Erb Well # 1Operator: Energy Three, Inc.County Ness 145.60Name & Address P. O. Box 1505Well Total Depth 4480 (Cherokee) feetGreat Bend, KS 67530Conductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 515Abandoned Oil Well Gas Well Input Well SWD Well D&A XOther well as hereinafter indicated Plugging Contractor Big Three Drilling, Inc. License Number 5836Address P. O. Box 52, Gorham, KS 67640Company to plug at: Hour: 4:00 pm Day: 8 Month: August Year: 1985Plugging proposal received from Johnny(company name) Big Three (phone) 913-637-5487Elevation 2240GLwere: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1490'1st plug at the base of the Anhydrite with 50 sx cement2nd plug at 800' with 50 sx cement3rd plug at 540' with 40 sx cement May set 650' of 8 5/8". Then will set 1 plug
solid bridge at 700' instead of 24th plug hulls - plug at 40' -- cement to surface with 10 sx cement6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with
10 sx cement Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 6:45 pm Day: 8 Month: August Year: 1985ACTUAL PLUGGING REPORT 1st plug at 1520' with 50 sx cement, 2nd plug at 800' with 50 sxcement, 3rd plug at 540' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plugat 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15sx cement, 7th plug to circulate mouse hole with 10 sx cement.Remarks: Used 60/40 Pozmix 6% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1985INV. NO. 98168-8 SEP 11 1985CONSERVATION DIVISION
Wichita, KansasSigned R. B. Tarbutton
(TECHNICIAN)