

1080076

To:

API NUMBER 15-135 - 22,491-0000

STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

C SE SE, Sec. 2, T 20 S, R 22 W/E

660 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name Erb Well # 1

Operator: Rains & Williamson Oil Co.
 Name & 435 Page Court, 220 West Douglas
 Address Wichita, KS 67202

County Ness

Well Total Depth 4515 feet 146.73

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Company Tools License Number 5146

Address 435 Page Court, 220 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 12:00 pm Day: 24 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Richard Phaff

(company name) Rains & Williamson (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 1520' with 50 sx cement

2nd plug at 400' with 50 sx cement
solid bridge

3rd plug at hulls - plug at 40' -- cement to surface with 10 sx cement.

5th plug to circulate rathole with 15 sx cement

Signed J. A. Mey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 pm Day: 24 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1520' with 50 sx cement, 2nd plug at 400' with

50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement. 5th plug to circulate rathole with 15 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. By Allied Cementing

RECEIVED
STATE CORPORATION COMMISSION

FEB 02 1984

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
 and that I (did / did not) observe this plugging.

Signed J. A. Mey (TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 2-6-84

INV. NO. 0076