


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

15-077-00027-0000

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 3 Twp. 32S Rge. 9 (X) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Petroleum Management, Inc. for C. J. Brown  
Lease Name Maroney Well No. 1  
Office Address 502 Braniff Bldg., Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-14-1955  
Application for plugging filed 3-23-1955  
Application for plugging approved 3-24-1955  
Plugging commenced 6-8-1955  
Plugging completed 6-11-1955  
Reason for abandonment of well or producing formation Commercially unprofitable  
If a producing well is abandoned, date of last production 3-27-1955  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rivas  
Producing formation Mississippi Depth to top 4355 Bottom \_\_\_\_\_ Total Depth of Well 4436 Feet  
Show depth and thickness of all water, oil and gas formations. PBTB 4393

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3490		8/ 5/8	200	NONE
Douglas		3570				
Mississippi		4355		5 1/2	4393	3809

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 4380' to 4350'. Run five sacks cement from 4350' to 4315'.  
Filled with Mud to 199' and Rock budge cap with ten sacks cement from 35' to cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service  
Address Hutchinson, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
John W. Ritchey (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John W. Ritchey  
810 Central Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1955

My commission expires April 23, 1958

Morgan C. Murphy  
RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.

JUN 17 1955  
CONSERVATION DIVISION  
Wichita, Kansas  
PLUGGING  
SEC 3 T 32 R 9W  
PAGE 12 LINE 10

DRILLER'S LOG

C. J. Brown  
#1 Jane Mareney  
SW SW SW 3-325-97  
Harper County, Kansas

<u>TO</u>	<u>FROM</u>	
0	202	Red Rock
202	715	Red Rock & Shale
715	1160	Salt & Shale
1160	1210	Shale & Shell
1210	1460	Shale & Lime
1460	2140	Lime & Shale
2140	2360	Shale & Lime
2360	2940	Lime & Shale
2940	3130	Lime
3130	3711	Lime & Shale
3711	4120	Lime
4120	4251	Lime & Shale
4251	4352	Lime
4352	4361	Lime & Shale
4361	4381	Mississippi
4381	4386	Lime
4386	4406	Coring
4406	4406	Reaming Core Hole
4406	4436	Coring
4436	4436	ROTARY TOTAL DEPTH

COMMENCED: 2-12-55  
COMPLETED: 3-3-55

CASING RECORD:

Set 100' of 8 5/8" surface casing with 150 sacks cement.  
Set 5 1/2" casing at 4391' with 100 sacks cement.

STATE OF KANSAS |  
COUNTY OF SEDGWICK |

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Jane Mareney located SW SW SW of Section 3-325-97, Harper County, Kansas.

ANDERITE DRILLING CO., INC.

BY: *E. S. Koelling*  
E. S. Koelling

Subscribed and sworn to before me this 7th day of March, 1955.

*[Signature]*  
Notary Public

My Commission Expires: July 28, 1958.

**PLUGGING**  
FILE SEC 3 T 32 R 9 W  
BOOK PAGE 12 LINE 10

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 22 1955  
CONSERVATION DIVISION  
Wichita, Kansas