


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-077-00205-0000  
WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 11 Twp. 32 Rge. (E) 9 (W)  
Location as "NE/CNW/SW" or footage from lines C NE NW  
Lease Owner Rupp-Ferguson Oil Co.  
Lease Name Weathered Well No. 1  
Office Address 522 Union Center, Wichita  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-26-58 19  
Application for plugging filed 3-26-58 19  
Application for plugging approved 3-26-58 19  
Plugging commenced 3-26-58 19  
Plugging completed 3-26-58 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4417 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	227	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed, and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 180, 1/3 sack hulls, plug, cement w/20 sax thru drill pipe. Mud to 35', 1/3 sack hulls, plug, cement w/10 sax.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 1958  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.  
Address 522 Union Center

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. W. Knox, ~~employee of owner~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. W. Knox*  
522 Union Center, Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 58

*Helen Horine*

My commission expires June 4, 1959 Notary Public.

PLUGGING  
FILE SEC. 11 T. 32 R. 9W  
BOOK PAGE 91 LINE 34

CONTRACTOR'S WELL LOG

Rupp-Ferguson No. 1 Weathered  
C. NE NE, Sec. 11-32-9W,  
Harper County, Kansas

Set 227' of 8 5/8" csg. w/175 sqn

D & A

Commenced: 3-15-58  
Completed: 3-26-58  
Contractor: Rupp-Ferguson Oil Co.

Figures Indicate Bottom of Formation

10 surface soil  
530 red bed  
740 reddish sand & red bed  
910 blue shale & shells  
1315 shale & shells  
1804 shale & lime  
1950 lime, shale & sand streaks  
3500 lime & shale  
3604 Douglas, sand, lime, shale  
3661 lime & shale  
3715 lime  
4377 shale & lime  
4392 chert & shale Cg.  
4417 cherty lime  
T.D.

STATE OF KANSAS)  
SEDGWICK COUNTY) SS:

I, L. W. Knox, Partner in Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Weathered well.

  
L. W. Knox

Subscribed and sworn to before me this 31st day of March, 1958.

  
Notary Public

My Commission Expires June 4, 1959.

RECEIVED  
BY TELEGRAPHIC COMPANY

APR 3 1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE NO. 11-T-32-R-9W  
BOOK PAGE 91 LINE 34