

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,423-0000

LEASE NAME SHAFT #

WELL NUMBER 3

 Ft. from S Section Line

 Ft. from E Section Line
 C S 1/2 NW 1/4

SEC. 19 TWP. 31 SRGE. 14 (XXX) (W)

COUNTY BARBER

Date Well Completed

Plugging Commenced 11-26-91

Plugging Completed 12-4-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR GOULD OIL, INC.

ADDRESS 110 NORTH MARKET WICHITA, KS. 67202

PHONE# (316) 265-5523 OPERATORS LICENSE NO. 5298

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on DEC. 3, 1991 (date)

by STEVE (KCC District Agent's Name)

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation VIOLA Depth to Top Bottom T.D. 4900

Show depth and thickness of all water, oil and gas formations.

PBTD: 4875

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION
 12-23-91
 DEC 23 1991

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|-----------------|
| | | 0 | | 13 3/8 | 66jts. | 0 |
| | | 0 | 976 | 8 5/8 | 976 | 0 |
| | | 0 | 4896 | 5 1/2 | 4896 | 2518FT. 76 JTS. |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

TOP OF SAND, 4245. DUMPED 5 SX CEMENT ON TOP OF SAND. SHOT OFF CASING AT 2518, 76 JTS. TOP HOLE PLUG: 300# HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8 PLUG, 100 SX. CEMENT, 60 40 POZ, 6% GEL. MAX PRESSURE ISIP 450#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of Operator ~~XXXXXXXXXXXXXXXXXXXX~~)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 20th day of Dec., 19 91

My Commission Expires: Feb. 6, 1993 Notary Public