

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-20,540-0000

LEASE NAME SHAFT

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #2

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR [Redacted] Gould Oil, Inc.

C SE 1/4-SE 1/4-NW 1/4
SEC. 19 TWP. 31S RGE. 14 W

ADDRESS 110 NORTH MARKET #411 WICHITA, KS. 67202

COUNTY BARBER

PHONE# (316) 265-5523 OPERATORS LICENSE NO. 5298

Date Well Completed

Character of Well OIL

Plugging Commenced 11-22-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-4-91

The plugging proposal was approved on DEC. 3, 1991 (date)

by STEVE (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation VIOLA Depth to Top Bottom T.D. 4705

Show depth and thickness of all water, oil and gas formations.

PBTD: 4650

12-23-91
DEC 23 1991

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	324	8 5/8	324	0
		0	4703	5 1/2	4703	2022 ft. -- 51 jts.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

RIGGED UP, DUMPED SAND TO 4470 FT., DUMPED 5 SX CEMENT ON TOP OF SAND. SHOT OFF CASING AT 2022 FT.

TOP HOLE PLUG: 300# HULLS, 10 SX. GEL, 50 SX. CEMENT, 10 SX. GEL, 100# HULLS, 8 5/8 PLUG

100 SX. CEMENT, 60-40 POZ, 6% GEL, MAX. PRESSURE 600# ISIP 200#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of [Redacted])
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Go PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 20th day of Dec., 19 91

Dorothy M. Furgason
Notary Public

My Commission Expires: Feb. 6, 1993