


15-007-00166-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 34 Twp. 31S Rge. (E) 14 (W)
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines NE NE SE
Lease Owner Jones, Shelburne & Farmer, Inc.
Lease Name LORA MILLS Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 12-15 19 55
Application for plugging filed 12-15 19 55
Application for plugging approved 12-15 19 55
Plugging commenced 12-15 19 55
Plugging completed 12-15 19 55
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Box 8 - Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4783 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


- Filled hole with heavy mud to bottom surface pipe
- Pushed plug to within 5 feet of bottom of surface pipe
- Pulled drill pipe
- Dumped in 1/2 sack hulls
- Ran drill pipe back in and cemented through drill pipe
- Cemented with 20 sacks on bottom, 10 sacks on top
- Filled hole with mud and then pushed plug to 35 feet
- Dumped in 1/2 sack hulls
- Dumped in 10 sacks through drill pipe to fill hole to top.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor D & M DRILLING COMPANY
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Russell
JOHN O. FARMER (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) John O. Farmer
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 55

My commission expires October 11, 1958 Notary Public.



LORA MILLS #1

NE/4 NE/4 SE/4 of Section 34-31S-14W Barber County, Kansas

Rigged up Rotary Tools 11/22/55

Ran 10 Jts. (206!) 8 5/8" - 28#
Used Casing set at 205'. Cemented
with 150 sacks common cement, 2
sacks Cal. Cl.

Tore down Rotary Tools 12/16/55

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
Redbed & shale	0'	680'	
Redbed	680	807	
Redbed & shale	807	1370	
Salt	1370	1475	
Shale & shells	1475	1545	
Lime & shale	1545	1590	
Shale & shells	1590	1770	
Shale & lime	1770	1995	
Cherty lime	1995	2030	
Lime & shale	2030	2175	
Lime	2175	2215	
Shale & lime	2215	2265	
Shale & shells	2265	2399	
Shale & lime	2399	3060	
Sandy lime & shale	3060	3105	
Lime & shale	3105	3280	
Lime	3280	3330	
Lime & shale	3330	3923	
Kansas City Lime	3923	4010	
Lime	4010	4628	
Lime & chert	4628	4640	
Lime	4640	4705	
Shale	4705	4734	
Shale & lime	4734	4775	
Lime	4775	4783	TD

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 22nd day of December, 1955.

John Swaney

My commission expires: July 29, 1957

12-29-55

John Swaney

PLUGGING
SEC 34-31-14W
PAGE 25 LINE 8