


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 31 Twp. 31S Rge. 14 ~~EW~~
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
NE $\frac{1}{4}$ NE SW
Lease Owner John C. Graves
Lease Name Mills Well No. 1
Office Address 910 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed September 9, 1976
Application for plugging filed September 9, 1976
Application for plugging approved September 9, 1976
Plugging commenced September 9, 1976
Plugging completed September 9, 1976
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes _____

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4898'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 250 feet. Pumped 35 sacks of cement through drill pipe with pump truck. Pushed plug and $\frac{1}{2}$ sack hulls to 40' and pumped 15 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1976

9-24-76
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.

Betty Brandt (employee of owner) or (operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt

910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 1976

Ruth N. Benjamin
Ruth N. Benjamin Notary Public

My commission expires June 17, 1977

15-007-20438-0000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: 28 Aug, 1976

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: 8 Sept. 1976

CASING RECORD: 6 Jts. 257' of used 8-5/8"
cemented with 185 sacks

LOCATION: Mills No. 1
NE NE SW
Section 31-31S-14W
Barber County, Kansas

0 - 760 Red bed
 760 - 1770 Red bed and shale
 1770 - 2340 Shale
 2340 - 2525 Shale and lime
 2525 - 2663 Lime
 2663 - 3020 Lime and shale
 3020 - 3125 Lime
 3125 - 4012 Lime and shale
 4012 - 4028 Shale and lime
 4028 - 4259 Shale and sand
 4259 - 4825 Lime and shale
 4825 - 4852 Lime
 4852 - 4898 Lime and shale
 4898 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1976
9-24-76
CONSERVATION DIVISION
Wichita, Kansas

GRAVES DRILLING CO., INC.

By John C. Graves President

STATE OF KANSAS)
SEDGWICK COUNTY)

SS:

Subscribed and sworn to before me, a Notary Public, this 17th day of September, 1976

My commission expires: February 2nd, 1980

Courtney M. Graves
Courtney M. Graves Notary Public

