


STATE OF KANSAS
STATE CORPORATION COMMISSION

15135-21824-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Ness County. Sec. 27 Twp. 19S Rge. 22 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SW

Lease Owner Zenith Drilling Corp., Inc.
Lease Name KUEHN Well No. 1
Office Address 505 Fourth Financial Center
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 07-05-1980
Application for plugging filed 07-05-1980
Application for plugging approved 07-05-1980
Plugging commenced 07-05-1980
Plugging completed 07-05-1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4440'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

T.D. 4440'

Set first plug at 780' with 70 sx.

2nd plug at 270' with 30 sx. and 40 sx. sand.

3rd plug at 140' with 10 sx., solid bridge,

5 sx & rathole.

Plug was down at 2:30 a.m. on 07-05-80.

RECEIVED
STATE CORPORATION COMMISSION
JUL 14 1980
7-14-80
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1980

My commission expires



Sherrie L. Brooks Notary Public.

CONTRACTOR'S WELL LOG

15135 21824 0000

OPERATOR: Zenith Drilling Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KUEHN #1
 LOCATION: NE SW, Section 27-19S-22W
 Ness County, Kansas
 SPUD DATE: 06-26-80
 COMPLETION DATE: 07-05-80

0	197	Sand & Shale
197	700	Shale
700	955	Sand & Shale
955	1156	Sand
1156	1503	Shale & Sand
1503	1541	Anhydrite
1541	1616	Shale & Sand
1616	3559	Shale
3559	4130	Shale & Lime
4130	4132	Lime
4132	4232	Shale & Lime
4232	4375	Lime
4375	4390	Shale & Lime
4390	4440	Lime
	4440	Rotary Total Depth

Spud hole at 3:30 p.m. on 06-26-80. Drilled 290' in a 12-3/4" hole. Ran 7 joints of 8-5/8" 20# casing (tally 281.11) Set at 287' KB. Cemented with 175 sacks of common cement, 2% gel, 3% c.c. Pumped plug to 273' K.B. Cement did circulate. Plug was down at 7:30 p.m. on 06-26-80.

T.D. 4440'. Set first plug at 780' with 70 sx. 2nd plug set at 270' with 30 sx. and 40 sx. sand. 3rd plug set at 140' with 10 sx., solid bridge, 5 sx. & rathole. 50/50 posmix, 6% gel. Plug was down at 2:30 a.m. on 07-05-80.

SAMPLE TOPS:

Anhydrite 1504'
 B/Anhydrite 1541'


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KUEHN #1, NE SW, Section 27-19S-22W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary public, in and for the aforesaid county and state as of this 8th day of July, 1980.



Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 14 1980
 CONSERVATION DIVISION
 Wichita, Kansas