

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Harper

County. Sec. 26 Twp. 34S Rge. (E) 5 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE NW

Lease Owner SUNRAY MID-CONTINENT OIL COMPANY

Lease Name Baker Well No. 1

Office Address Box 788, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 30 19 57

Application for plugging filed December 3 19 57

Application for plugging approved December 4 19 57

Plugging commenced November 30 19 57

Plugging completed November 30 19 57

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene Graham

Producing formation Depth to top Bottom Total Depth of Well 4938 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	280	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy drilling mud, set plug at 240' with 15 sacks cement.  
Filled hole with heavy drilling mud, set plug at 30' with 10 sacks cement.  
Job completed.

Well log attached.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 1 6 1957

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

N. E. Montgomery (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. E. Montgomery

Box 788, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 57

Notary Public

My commission expires December 24, 1960

PLUGGING  
FILE SEC 26 T 34 R 5W  
BOOK PAGE 65 LINE 31

Sunray Mid-Continent Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
December 3, 1957

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: November 5, 1957  
Drilling Completed: November 30, 1957

W. Baker #1 W/2 of Sec.  
26-34S-5W, Rainbow Bend  
Group, Bluff Creek Field  
Area, Harper Co., Kansas.

DRILLERS LOG

Depth Figures indicate base of formation:

Surface	0
Surface Clay & Sand	40
Shale & Shells	265
Shale & Red Bed	281 <sup>0</sup>
Shale & Red Bed & Shells	320
Shale & Shells	835
Anhydrite	875
Shale & Shells	955
Lime & Shale Streaks	1240
Shale & Lime	1405
Lime	1770
Lime & Shale	1935
Shale	2110
Shale & Lime	2265
Lime & Shale	2545
Shale & Lime	2710
Lime & Shale	2850
Sandy Lime	3010
Lime & Shale	3090
Sandy Lime & Shale	3240
Shale & Lime	3345
Lime & Shale	3655
Sandy Lime & Shale	3725
Lime & Shale	3814
Lime	3850
Kansas City Lime	3885
Lime	3952
Lime & Shale	4058
Shale	4182
Shale & Lime	4225
Lime & Shale	4370
Shale	4461
Mississippi Lime	4467
Mississippi Lime & Chat	4480
Lime	4522
Mississippi Lime	4535
Lime	4563
Mississippi	4578
Lime	4662
Mississippi Lime	4678
Lime	4841
Lime & Shale	4875
Shale	4913
Shale & Lime	4932
Lime & Shale	4933
Sand	4938 TD

STAT. DIV.

DEC 10 1957

CONSERVATION DIVISION  
Tulsa, Oklahoma

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's W. Baker #1 W/2 of Section 26-34S-5W, Rainbow Bend Group, Bluff Creek Field Area, Harper County, Kansas.

*Frank E. Stickle*  
Frank E. Stickle

*Lillian T. Benham*  
Notary Public

February 13, 1960  
My Commission Expires

PLUGGING
FILE SEC 26 T 34 R 5W
BOOK PAGE 65 LINE 34