

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Strike out upper line
when reporting plugging
off formations.

Harper County. Sec. 21 Twp. 34S Rge. 5 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. 330'

Lease Owner. J.M. Huber Corporation

Lease Name. Louis Misak Well No. 1

Office Address. 302 Petroleum Bldg., Wichita 2, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed. August 9th 19 46

Application for plugging filed. August 9th 19 46

Application for plugging approved. August 9th 19 46

Plugging commenced. August 9th 19 46

Plugging completed. August 9th 19 46

Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee

Producing formation. None Depth to top. Bottom. Total Depth of Well. 5310 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS


CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle				10-3/4" (cemented to surface)	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

10 sacks of cement 200' back.
5 sacks of cement on top of surface pipe.

PLUGGING
FILE SEC 21 34R 5W
BOOK PAGE 66 LINE 30



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Goodpaster Drilling Company, Mr. Herbert Goodpaster
Address P.O. Box 518, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Herbert Goodpaster (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *Herbert Goodpaster*

P.O. Box 518, Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of August, 19 46

My commission expires June 7th, 1950

Notary Public.

FARM: Misak #1
 LOCATION: NE NE SE 21-34S-5W Harper County, Kansas
 COMMENCED: June 28, 1946
 COMPLETED: August 9, 1946

200' of 10 3/4" surface pipe cemented to top
 200' to 325' Red Shale
 325' to 951' Blue Shale
 951' to 1055' Shale and Shells
 1055' to 1200' Broken Lime
 1200' to 1555' Lime and Shale
 1555' to 1640' Shale and Anhydrite
 1640' to 1835' Shale and Lime
 1835' to 1890' Shale and Gray Lime
 1890' to 1918' Soft White Lime
 1918' to 2950' Lime and Shale
 2950' to 2990' Lime
 2990' to 3088' Shale and Lime
 3088' to 3153' Lime Hard
 3153' to 3198' Shale and Lime Hard
 3198' to 3205' Lime Soft
 3205' to 3229' Shale and Lime Hard
 3229' to 3370' Shale and Lime
 3370' to 3573' Shale
 3573' to 3574' Lime and Shale
 3574' to 3608' Sand and Shale
 3608' to 3635' Lime and Shale
 3635' to 3665' Lime
 3665' to 3686' Hard Lime and Shale
 3686' to 3698' Sandy Lime
 3698' to 3702' Hard Lime and Shale
 3702' to 3776' Sandy Shale and Lime
 3776' to 3821' Sandy Shale
 3821' to 3858' Shale and Sand Streaks
 3858' to 3950' H. C. Lime
 3950' to 3979' Hard Lime and Shale
 3979' to 4044' Lime Hard
 4044' to 4372' Shale and Lime
 4372' to 4539' Shale
 4539' to 4555' Chert and Miss. Lime
 4555' to 4579' Miss. Lime
 4579' to 4682' Lime and Shale
 4682' to 4641' Lime
 4641' to 4646' Chert
 4646' to 4710' Lime
 4710' to 4734' Lime and Shale
 4734' to 4756' Lime Soft
 4756' to 4739' Lime and Shale
 4739' to 4795' Lime
 4795' to 4797' Chert
 4797' to 4843' Lime and Chert
 4843' to 5170' Lime
 5170' to 5290' Sand and Lime (Arbuckle)
 5290' to 5310' Sand and Lime
 5310' Total Depth. Plugged and Abandoned

PLUGGING
 FILE NO. 21 34 5W
 BOOK PAGE 66 LINE 30

AUG 29 1946

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

The Goodpaster Drilling Company, contractor of the above described well, being first sworn on oath, states that: I have knowledge of the facts, statements, and matters herein contained and the log of the attached described well as filed and that the same are true and correct, so help me God.

Hubert Goodpaster
Contractor

Subscribed and sworn to before me this 20th day of
August, 1946.

My Commission Expires:

June 7, 1950

Annette Syrell
Notary Public

AUG 29 1946