

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Harper County, Sec. 21 Twp. 34S Rge. 5W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner The Texas Company

Lease Name L. R. Bird Well No. 1

Office Address 614 Bitting Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed August 23 19 53

Application for plugging filed (Verbal 8-23) August 24 19 53

Application for plugging approved (Verbal 8-23) August 25 19 53

Plugging commenced August 23 19 53

Plugging completed August 24 19 53

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes Mr. T. A. Morgan

Name of Conservation Agent who supervised plugging of this well Mr. Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 4596' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	604'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGED AS FOLLOWS

4596' to 600' - Heavy Mud
600' to 540' - 25 Sacks Cement
540' to 28' - Heavy Mud
28' to Bottom of Cellar - 10 Sacks Cement

Name of Plugging Contractor Stickle Drilling Company
Address 507 Bitting Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
M. C. Harrell (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell
614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 19 53

My commission expires September 20, 1956 H. Howard Kistler Notary Public.

PLUGGING
FILE SEC 21 T 34 R 5W
BOOK PAGE 124 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
SEP - 3 1953
CONSERVATION DIVISION
Wichita, Kansas

LOG OF WELL

SHEET NO. 2

District Kansas Owner The Texas Company Farm L. R. Bird Well No. 1

FORMATION	AMOUNT	COLOR	HARD OR SOFT	DEPTH CORES TAKEN	REMARKS
<u>REMARKS:</u>					
8-11-53	Ran DST #1	from 3185-3200'	open 1 hour,	recovered 10'	drilling mud. SBHP 157' in 15 minutes.
8-16-53	Ran DST #2	from 3650-70'	open 1 hour,	recovered 30'	drilling mud. SBHP 1478' in 15 minutes.
8-23-53	Drilled to	4596'	ran Schlumberger	Survey.	
8-24-53	Plugged and	abandoned.			
<u>TOPS:</u>					
Topeka-----2650					
Douglas-----3226					
Stalnaker-----3594					
Kansas City-----3843					
Layton-----3847					
Layton Sd.-----3860					
K. C. Line-----3873					
Base K.C.-----4095					
Marmaton-----4193					
Cherokee-----4332					
Mississippi-----4568					

The Texas Company
Tulsa, Oklahoma

Tulsa, Oklahoma
August 31, 1953

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: August 1, 1953
Drilling Completed: August 23, 1953

L. R. Bird #1 NW-NW-SE-
Section 21-34S-5W, Harper
County, Kansas.

DRILLERS LOG

Shale & Red Bed	0-450
Shale & Shells	450-900
Shale & Lime	900-1430
Lime & Shale	1430-1915
Shale & Lime	1915-2090
Lime & Shale	2090-2661
Lime	2661-2775
Lime & Shale	2775-3118
Lime	3118-3167
Lime & Shale	3167-3200
Sandy Lime & Shale	3200-3254
Shale & Lime	3254-3635
Sandy Shale & Lime	3635-3674
Sandy Lime & Shale	3674-3733
Sand & Shale	3733-3745
Shale	3745-3803
Shale & Lime	3803-3856
Sand	3856-3870
Sand & Lime	3870-3903
Lime	3903-4120
Shale & Lime	4120-4350
Lime & Shale	4350-4376
Shale & Lime	4376-4416
Shale	4416-4465
Shale & Lime	4465-4543
Lime & Shale	4543-4581
Lime	4581-4600 TD
Corrected T.D.	4596'

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of The Texas Company's L. R. Bird #1 NW-NW-SE-Section 21-34S-5W, Harper County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1956

My Commission Expires

STATE OF KANSAS

CONSERVATION DIVISION
Tulsa, Kansas

PLUGGING
FILE SEC 21 T 34 R 5 W
BOOK PAGE 124 LINE 28