

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Harper

County. Sec. 15 Twp. 34S Rge. 5 (X) (W)

Location as "NE/CNW/SW" or footage from lines C SW SW SW

Lease Owner FALCON SEABOARD DRILLING COMPANY

Lease Name HRANICKA Well No. 1

Office Address Stanolind Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 30, 19 56

Application for plugging filed March 30, 19 56

Application for plugging approved March 30, 19 56

Plugging commenced March 30, 19 56

Plugging completed March 31, 19 56

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	620	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran half of drill pipe in hole, gun pits and raise heavy mud and circulate in hole. Pulled drill pipe and left four stands in derrick. Made solid bridge of hulls in surface pipe coming up to approximately 250 feet. Spotted 20 sacks cement at 250 feet through four stands of drill pipe and pulled out. Filled up on top of cement plug with mud 30 feet and built up another solid bridge of hulls. Spotted 5 sacks cement in top of surface casing from top of bridge.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor FALCON SEABOARD DRILLING COMPANY

Address Stanolind Building, Tulsa, Oklahoma.

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

J. O. Brown

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Brown

Stanolind Building, Tulsa, Oklahoma.

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 19 56.

My commission expires February 8, 1958.

RECEIVED
STATE CORPORATION COMMISSION

Notary Public.

APR 4 - 1956

PLUGGING

FILE SEC 15 T 34 R 5W
PAGE 51 LINE 14

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY - Falcon Seaboard Drilling Company

Sec. 15-34S-5W

FARM - Hranicka No. 1

Loc. SW SW SW

TOTAL DEPTH - 5074'

County - Harper

COMM. 3-4-56. COMP. 3-30-56

CONTRACTOR - Company Tools

ELEVATION

D.F. - 1218
Gr. - 1211

CASING

10-3/4" - 620'

DRILLER'S LOG

Sand & Red Bed	0	610
Shale	610	900
Shale & Lime	900	1090
Lime	1090	1278
Lime & Shale	1278	1850
Shale & Shells	1850	2230
Lime & Shale	2230	3560
Shale, Lime & Sand	3560	3615
Lime & Shale	3615	3755
Shale	3755	3862
Lime	3862	3957
Shale & Lime	3957	4178
Lime	4178	4224
Shale	4224	4535
Lime	4535	4957
Lime & Shale	4957	4988
Shale	4988	5033
Dolomite	5033	5055
Sand	5055	5074
Total Depth	5074	

This is to certify that the foregoing is a true and correct copy of the Hranicka No. 1 Well Driller's Log, as it is recorded in the log books of Falcon Seaboard Drilling Company.

J. O. Brown
J. O. Brown

Subscribed and sworn to before me this 3rd day of April, 1956.

Dolores Welsh
Notary Public

My commission expires February 8, 1958.

RECEIVED
STATE COMMISSION

APR 4 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 15 T 34 R 5W
BOOK PAGE 51 LINE 14