

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,717

LEASE NAME Schaben

WELL NUMBER #1-1

SPOT LOCATION 100'W SE SE

SEC. 1 TWP. 19 RGE. 22 (E) of (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 12-8-84

Plugging Completed 12-13-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR W. L. Kirkman, Inc.

ADDRESS Box 982, Pratt, Ks. 67124

PHONE # (672)- 7471 OPERATORS LICENSE NO. 5673

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4355'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	250'	None
				5-1/2"	4,354'	2,119.92'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 4240' and 5 sacks cement Shot casing at 3400', 3000', 2750', 2500', 2250' and 2000'. Pulled 52 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 15 sacks gel, 70 sacks cement 10 sacks gel, 1 sack hulls, released plug and pumped 160 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 750 psi and shut in 250 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Gt. Bend, Ks. 67530

RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton

12-28-84
DEC 28 1984

James W. Rockhold (employee of operator) (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 18th day of December, 1984

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

My Commission expires: _____

ALDEBARAN



433 SOUTH WIEBE ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

15135-22717-0000

WELL LOG

WELL NAME: SCHABEN #1-1

WELL LOCATION: C SE SE

SEC. 1-19S-22W NESS COUNTY, KS.

COMMENCED: 6:00 P.M. 11-8-84

COMPLETED: 7:00 A.M. 11-16-84

OPERATOR: W.L. KIRKMAN, INC.

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

6 Jts. 8 5/8" 23 wt. new set
CASING RECORD: at 250' 175 sks.
common 2% gel 3% cc. - 108 jts.
5 1/2" 14 wt. new/used set at
4354' 150 sks. 60-40 poz. 18%
salt 3/4 of 1% CFR-2 500 gal.
mud sweep

FORMATION:

FROM:

TO:

Post Rock	0	60
Shale	60	259'
Sand-Red Bed	259'	940'
Red Bed	940'	1800'
Shale-Red Bed	1800'	2322'
Lime-Shale	2322'	4335'

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1984

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED

C SE SE, SEC. 1-19S-22W, NESS COUNTY, KANSAS TO THE BEST OF MY

KNOWLEDGE AND BELIEF.

ALDEBARAN DRILLING CO., INC.
WAYNE L. KIRKMAN
PRESIDENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20TH DAY OF NOVEMBER, 1984

KATHLEEN G. QUINN
APPOINTMENT EXPIRES MARCH 20, 1987

KATHLEEN G. QUINN

3-20-87