


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 34 Twp. 32 Rge. 13 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C/NW $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Lee Phillips Oil Co.
Lease Name Mee Well No. 1
Office Address 125 N. Market, Suite 1532, Wichita, Kans. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole



Locate well correctly on above
Section Plot

Date Well completed 11-5 19 81
Application for plugging filed 11-5 19 81
Application for plugging approved 11-5 19 81
Plugging commenced 11-5 19 81
Plugging completed 11-5 19 81
Reason for abandonment of well or producing formation
dry

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4610
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	346	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Plug with 110 sacks 50-50 posmix, 4% Gel, 3% CC.
50 sacks @ 1120, 40 sacks @ 320, 10 sacks @ 40, 10 sacks in rat hole.
Plug down at 10:30 P.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Nelle A. Salmon (employee of owner) or (owner or-operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Nelle A. Salmon
125 N. Market, Suite 1532, Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1981



My commission expires May 10, 1984.

Celine Oaks
Notary Public.
STATE CORPORATION COMMISSION

NOV 17 1981

CONSERVATION DIVISION
Wichita, Kansas

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Well #1
 N/2 Sec 34-32S-13W
 Barber County Kansas

Commenced: 10-26-81

Completed: 11-5-81

OPERATOR: LEE PHILLIPS

Depth		Formation	Remarks
From	To		
0	445	Redbed-Gyp-Shale	Ran 8 jts of 24# 8-5/8" csg set @ 346' Cemented w/ 275 sks Common 2% Gel 3% CC PD @ 5:15 p.m. 10-26-81
445	1221	Shale-Shells	
1221	1960	Shells-Shale	
1960	2504	Shale	
2504	2688	Shale-Lime	
2688	3015	Lime-Shale	
3015	3524	Shale	
3524	4029	Shale-Lime	
4029	4415	Lime-Shale	
4415	4582	Shale-Lime	
4582	4610	Shale-Lime-Chert	
	4610 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 10th day of November, 1981.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

5177
 01

RECEIVED
 STATE CORPORATION COMMISSION

CONSERVATION DIVISION
 Wichita, Kansas