

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

2

API NUMBER 15-077-21,239-00-00

LEASE NAME Faye

WELL NUMBER 1-11

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 11 TWP. 34 RGE. 6 (E) or (W)

COUNTY Harper

Date Well Completed 4-19-91

Plugging Commenced 4-19-91

Plugging Completed 4-19-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Carl E. Gungoll Exploration, Inc.

ADDRESS 14000 Quail Springs Parkway, Suite 220

Oklahoma City, OK 73134

PHONE# (405) 755-1179 OPERATORS LICENSE NO. 30672

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-17-91 (date)

by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out

APR 25 1991

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 950' w/35 sacks cement thru drill pipe

Next Plug: @ 650' w/35 " " " " " 10 sacks in Rat Hole

Next Plug: @ 350' w/35 " " " " " 10 sacks in Mouse Hole

Top Plug: @ 60' w/5 " " " " " (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lobo Drilling Company

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors

(Employee of Operator) or ~~XXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 91

Paula Ann Laudick
Notary Public

My Commission Expires:



DRILLER'S WELL LOG

DATE COMMENCED: April 9, 1991
DATE COMPLETED: April 19, 1991

Carl E. Gungoll Exploration, Inc.
PAYE #1-11
NE NE SE
Sec. 11, T34S, R6W
Harper County, Ks.

0 - 1274' Surface Soil, Red Bed, Shale
1274 - 2715' Shale & Lime
2715 - 4503' Lime & Shale
4503 - 5000' Shale & Lime
5000' RTD

ELEVATION: 1240 K.B.

Surface Pipe: Set used 10-3/4"
pipe @ 54' w/20 sacks 60/40 pozmix
2% gel, 3%cc & Set new 8-5/8"
20# pipe @306' w/150 sacks
60/40 pozmix 2% gel 3%cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and
statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 29th day of April 1991.



Paulanne Laudick
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1991

CONSERVATION DIVISION
Wichita, Kansas