

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 135-24046 0000

LEASE NAME Schaben

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
2310 Ft. from S Section LI
2970 Ft. from E Section LI

LEASE OPERATOR OBRIEN ENERGY RESOURCES CORPORATION

SEC. 26 TWP. 19SRGE.22W ~~(N)~~ or (W)

ADDRESS 75 Congress Street Portsmouth, New Hampshire 03801

COUNTY Ness

PHONE (800) 291-1969 OPERATORS LICENSE NO. 32211

Date Well Completed 3/12/98

Character of Well D&A

Plugging Commenced 1:00PM 3/12/98

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 4:15PM 3/12/98

The plugging proposal was approved on 3/10/98 (dat
by Steve Middleton (KCC District Agent's Name

Is ACO-1 filled? Yes If not, is well log attached? Yes

Producing Formation None Depth to Top Bottom T.O. 4450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORD

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	307	8 5/8	307.42	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed, from feet to feet each
1st Plug @ 1540' w/50sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes with 49 Vis Mud
2nd Plug @ 700' w/80sks 15sks In Rat Hole Plugs displaced with mud.
3rd Plug @ 330' w/40sks Total 205sks 60/40Poz 6%Gel W/1#FS/sk By Halliburton
4th Plug @ 40' w/10sks Completed @ 4:15PM 3/12/98

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OBRIEN ENERGY RESOURCES CORPORATION

STATE OF New Hampshire COUNTY OF Rockingham, ss.

John Forma

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fa
statements, and matters herein contained and the log of the above-described well as filed
the same are true and correct, so help me God.

(Signature) John Forma

(Address)

SUBSCRIBED AND SWORN TO before me this 20 day of March, 19 98

Heidi L. Byers
Notary Public

RECEIVED
STATE OF KANSAS
3-31-98
MAR 31 1998
CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires: HEIDI L. BYERS, Notary Public

USE ONLY ONE SIDE OF EACH FORM My Commission Expires August 6, 2002