

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15:135-20160-0000

API NUMBER 7/24/68

LEASE NAME Gillig

WELL NUMBER #1

150' NE of C NE SE
2100 Ft. from S Section Line

560 Ft. from E Section Line

SEC. 26 TWP. 19 SRGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed 7/24/68

Plugging Commenced 7/12/94

Plugging Completed 7/12/94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Knighton Oil Company, Inc.

ADDRESS 221 South Broadway-#710, Wichita, Kansas

PHONE#(316) 264-7918 OPERATORS LICENSE NO. 5010 ⁶⁷²⁰²

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/12/94 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Mississippian Depth to Top 4373 Bottom 4401 T.D. 4401

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Oil	Surface	489	8-5/8"	489'	None
		"	4396	4 1/2"	4396'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mixed 200# Hulls, 20 sx cement, displaced with 15 sx Gel and 21 Bbl. water.

Pressured to 1600# and plug held. Perforated 4 1/2" @ 800' and mixed 240 sacks 60/40 Pozmix, 6% Gel. Pumped down 4 1/2" and filled annulus and 4 1/2" casing from 800 to Surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: KNIGHTON OIL COMPANY, INC.

STATE OF: KANSAS COUNTY OF SEDGWICK, ss.

Earl M. Knighton, Jr. (Employee of Operator) or Wichita, Kansas

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Earl M. Knighton, Jr.

(Address) 221 South Broadway-#710
Wichita, Kansas 67202

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 94


Sarah A. Simon

Notary Public
Sarah A. Simon

My Commission Expires: 12/11/97

RECEIVED
STATE CORPORATION COMMISSION
JUL 25 1994

CONSERVATION DIVISION of
WICHITA, KANSAS



DRILLER'S LOG

COMPANY: Brandt-Clark Oil Company, 737 1st Natl. Bank Bldg., Wichita, Ms.
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas
 LEASE: #1 Gillig
 LOCATION: Approx. C NE SE 26-19S-22W, Ness County, Kansas
 COMMENCED: June 29, 1968
 COMPLETED: July 9, 1968
 CASING: Set 3 5/8" Surface Casing @ 439'/280 sacks cement
 Set 4 1/2" Casing @ 396 1/2'/200 sacks cement

0-490	Sand and Shale
490-1280	Shale & Sand
1280-1507	Shale & Red Bed
1507-1547	Anhydrite
1547-2040	Shale & Red Bed
2040-2379	Shale & Lime
2379-3794	Lime & Shale
3794-3915	Lime & Shale (L.-K.C.)
3915-4085	Lime & Shale
4085-4155	Lime
4155-4373	Lime & Shale
4373-4401	Mississippian
4401	Rotary Total Depth

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Gillig, located Approx. C NE SE Sec. 26-19S-22W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

RECEIVED
 STATE CORPORATION COMMISSION

JUL 25 1968

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, this 15th day of July, 1968.

CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires:
 March 25, 1970

Catherine Darcy
 Notary Public - Catherine Darcy

