


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 24 Twp. 19S Rge. 22W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner Petroleum Management, Inc.
Lease Name Schaeben Well No. 1
Office Address 1515 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-15-65 19
Application for plugging filed 1-15-65 19
Application for plugging approved 1-15-65 19
Plugging commenced 1-15-65 19
Plugging completed 1-15-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4382 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 422' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1965
1-20-65
CONSERVATION DIVISION
Wichita, Kansas

1st Plug @ 540' with 20 sks. cement through drill pipe
2nd Plug @ 240' with 20 sacks cement through drill pipe
3rd Plug @ 40' with 10 sacks cement & 1/2 sk. hulls

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1965

Ulauda Spidala
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

COMPANY: Petroleum Management, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SCHAEBEN #1
 LOCATION: C SE SE Sec. 24-19S-22W
 NESS COUNTY, KANSAS
 COMMENCED: 1-4-65
 COMPLETED: 1-15-65

| | | |
|------|-------------|---|
| 0 | 185 | Post Rock Shale |
| 185 | 255 | Sand |
| 255 | 422 | Blue Shale |
| 422 | 580 | Shale |
| 580 | 950 | Redbed |
| 950 | 1095 | Sand |
| 1095 | 1420 | Shale & Redbed |
| 1420 | 1425 | Shale |
| 1425 | 1480 | Anhydrite |
| 1480 | 2280 | Shale & Shells |
| 2280 | 2420 | Shale & Lime |
| 2420 | 3275 | Lime & Shale |
| 3275 | 3390 | Shale |
| 3390 | 3700 | Lime & Shale |
| 3700 | 4382 | Lime |
| | <u>4382</u> | <u>Rotary Total Depth - D. & A.</u> |

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 20 1965
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" new 20# surface casing @ 422 with 275 sacks Common 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schaeben #1 well, located C SE SE of Section 24, Township 19 South, Range 22 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to me this 19th day of January, 1965, in and for Barton County, Kansas.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires
 April 1, 1967