

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135.22.846-0000

LEASE NAME Wegele

WELL NUMBER #1

SPOT LOCATION 3630 FSL
990 FEL

SEC. 24 TWP. 19 RGE. 22 (NW or (W)

COUNTY Nass

Date Well Completed 6-29-85

Plugging Commenced 6:30 PM

Plugging Completed 8:30 PM
6-29-85

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Dreiling Ltd. of Colorado
 ADDRESS 410 - 17th St., Suite 1140, Denver, Co. 80202

PHONE # (303) 623-6144 OPERATORS LICENSE NO. 5804

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? No logs taken

Producing formation None Depth to top _____ bottom T.D. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	25' SOCM free oil on top	4327	4340	8-5/8	431	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Hole full of heavy mud (visc 52) pumped cement through drip pipe as follows: 1st cement plug at 1440' with 50 sacks, 2nd cement plug 720' with 60 sacks, 3rd cement plug at 420' with 50 sacks, 4th wood and rubber plug with 10 sacks cement from 40' to surface, 15 sacks in rathole, 10 sacks in mousehole, 195 sacks pozmix total with 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287
 Address Hays, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

Les Olson (employee of operator) or
~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That
 I have knowledge of the facts, statements, and matters herein contained and
 the log of the above-described well as filed that the same are true and
 correct, so help me God,

(Signature) Les Olson
 (Address) 410 - 17th St., Suite 1140
Denver, Colorado 80202

SUBSCRIBED AND SWORN TO before me this 7th day of July, 1985

Notary Public

My Commission expires: 9-2-87

RECEIVED
 STATE CORPORATION COMMISSION Form CP-4 1-84
 Revised 06-83

AUG 7 1985
 8-7-85
 CONSERVATION DIVISION
 Wichita, Kansas