

15-135-30241-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 23 Twp. 19 Rge. 22 (E) (W)

Location as "NE/CNW&SW" or footage from lines C SE SE

Lease Owner Quality Oil Company

Lease Name Gillig Well No. A2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 3/20/67 19

Plugging completed 3/25/67 19

Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 4409 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	402	none
				4 1/2	4396	2482

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran sand to 4380', dumped 4 sacks of cement. Shot pipe at 3618', 3381', 3272'. Pumped 80 barrels of oil, shot pipe at 2867', 2773', 2675', 2563', 2480'. Worked pipe loose. Set 10' rock bridge at 390', dumped 5 sacks of cement. Bailed hole to 390', dumped 6 yards of ready mix, tallied pipe. Loaded unit and capped hole with 10 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 5 1967  
4-5-67  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss. NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 1967

My commission expires February 15, 1971

Margaret Melcher  
Notary Public.

**ROTARY DRILLING LOG**

COMPANY: **Pickrell Drilling Company** Rotary Drilling Commenced 8/11/66  
 705 Fourth National Bank Bldg.  
 Wichita, Kansas Rotary Drilling Completed 8/21/66

LOCATION: **Gillig "A" No. 2**  
**C SE SE Section 23-19S-22W**  
**Ness County, Kansas**

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
**Wichita, Kansas**

CASING RECORD: **(19 Jts.) 8 5/8" surface casing set at 402' with 175 sacks cement.**  
**Circulated. Set (140 Jts.) 4 1/2" casing at 4396' with 155 sacks cement.**  
**Completed 10:45 PM, August 21, 1966.**

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Top Soil & Clay	<u>C. F. S.</u>
403	Shale & Shells	4382
670	Shale, Shells & Sand	4385
945	Red Beds, shale, Blaine	4406
1155	Sand	
1498	Shale & Shells	
1541	Anhydrite	<u>Slope Test</u>
2160	Shale & Shells	2000
2515	Lime & Shale	2500
2655	Lime	3000
3595	Shale & Lime	3500
3745	Shale	4000
3974	Lime & Shale	
4125	Lime	
4185	Lime & Shale	
4334	Lime	<u>S. L. M.</u>
4385	Lime & Chert	Board 4005.53
4406	Mississippian - RTD	Strap 4003.74
		Diff. 1.79

RECEIVED  
 MAR 20 1967  
 REGISTRATION DIVISION  
 Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for **PICKRELL DRILLING COMPANY**, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

**PICKRELL DRILLING COMPANY**  
 By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss:

On this 24th day of August, 1966, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of **PICKRELL DRILLING COMPANY** to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires May 10, 1970

L. M. Whiting  
 L. M. Whiting, Notary Public