

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County, Sec. 23 Twp. 19S Rge. (E) 22 (W)

Location as "NE/CNW%SW%" or footage from lines C/NW NE

Lease Owner Thunderbird Drilling, Inc.

Lease Name Sekavec Well No. 1

Office Address Box 18407, 4328 East Kellogg, Wichita, Kansas 67218

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 11 19 74

Application for plugging filed July 11 19 74

Application for plugging approved July 11 19 74

Plugging commenced July 11 19 74

Plugging completed July 11 19 74

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4411 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	285'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 550' with 50 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 25 sacks of 50-50 pozmix and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 12:45 P. M. July 11, 1974.

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON, ss.


Kenneth J. Link (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth J. Link
Kenneth J. Link
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 12th day of July, 19 74

My commission expires December 14, 1977

Elaine H. Taylor
Elaine H. Taylor Notary Public.



15 135 20917 0000

D R I L L E R S L O G

#1 Sekavec

CASING RECORD:
281.59' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/NW NE
Section 23-19S-22W
Ness County, Kansas

TOTAL DEPTH:
4411'

COMMENCED: July 1, 1974
COMPLETED: July 11, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock & Shale	0	300	Ran 281.59' os used 8-5/8" surface casing; set and cemented at 285' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at at 5:30 P. M. July 2, 1974.
Shale, Sand, Shells & Clay	300	800	
Shale & Sand	800	1365	
Anhydrite	1365	1740	
Lime & Shale	1740	4290	
Lime, Shale & Sand	4290	4330	
Lime & Shale	4330	4411	

ROTARY TOTAL DEPTH: 4411'

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1974
CONSERVATION DIVISION
Wichita, Kansas

Ran electric log.

D. & A.

Hole plugged as follows: Plugged at 550' with 50 sacks of 50-50 pozmix and 6% gel; plugged at 240' with 25 sacks of 50-50 pozmix; and 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 6% gel. Plug down at 12:45 P. M. July 11, 1974.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)


I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link

Subscribed and sworn to before me this 12th day of July, 1974.

My Commission Expires:



Elaine H. Taylor
Elaine H. Taylor, Notary Public