

15735-30217-6000

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 35 Twp. 19S Rge. (E) 22 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Rains & Williamson Oil Co.

Lease Name Ficken Well No. 1

Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-25 19 66

Application for plugging filed 3-25 19 66

Application for plugging approved 3-25 19 66

Plugging commenced 3-25 19 66

Plugging completed 3-25 19 66

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4462 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	358.05'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 450'. Cement with 20 sacks cement. Mud back to 350' set plug and cement with 20 sacks. Mud back to 40' set solid bridge and capped with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza Bldg., Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Wilson Rains, Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains  
Wilson Rains, Partner  
1425 Wichita Plaza Bldg. Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 66

Mary J. Brown  
Mary J. Brown Notary Public.

My commission expires 3-3-70



ROTARY DRILLING LOG

15-135-30217 0000

Operator: Rains & Williamson Oil Co.	Contractor: Rains & Williamson Oil Co.
#1 Ficken	Commenced: 3-16-66
C NE NE Section 25-19S-22W	Completed: 3-25-66
Ness County, Kansas	Remarks: Set 358.05' of 8-5/8" surface casing with 190 sacks of GL4 cement.

FORMATIONS:

Soil & Clay	40°
Shale	940°
Sand	1150°
Shale & Red Bed	1500°
Anhydrite	1541°
Shale	1825°
Lime w/shale	1925°
Shale & Shells	2210°
Shale & Lime	2460°
Lime	2755°
Lime & Shale	3135°
Shale & Lime	3810°
Lime & Shale	4240°
Lime	4280°
Lime & Shale	4350°
Lime	4420°
Lime & Shale Chert	4440°
Lime	4462°
Rotary Total Depth (D & A)	4462°

RECEIVED  
STATE CORPORATION COMMISSION

MAR 29 1966

CONSERVATION DIVISION  
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 28th day of March, 1966.

My Commission Expires: 3-3-70

*Mary J. Brown*  
Mary J. Brown Notary Public