
15-135-21915-0000 FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plat

Ness County. Sec. 34 Twp. 19S Rge. 22W E/W
Location as "NE/CNW¼SW¼" or footage from lines C SW NE
Lease Owner Pintail Petroleum
Lease Name Foos Well No. #1
Office Address 405 Century Plaza Bldg. Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole
Date Well completed December 31, 1980 19
Application for plugging filed December 31, 1980 19
Application for plugging approved December 31, 1980 19
Plugging commenced December 31, 1980 19
Plugging completed December 31, 1980 19
Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4480'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:
70 sacks @ 780', 25 sacks @ 330',
hulls and 10 sacks @ 40', 2 sacks
in mousehole, 3 sacks in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.

Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1981

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-84

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1981
CONSERVATION DIVISION
Wichita, Kansas

15-135-21915-0000

D R I L L E R S L O G

#1 Foos

CASING RECORD:
17 jts. new 24#
8-5/8" surface
casing

TOTAL ROTARY
DEPTH: 4480'

COMPANY: Pintail Petroleum

CONTRACTOR: Strata Drilling Company

COMMENCED: December 22, 1980

COMPLETED: December 31, 1980

D & A

DESCRIPTION: C SW NE
Section 34-19S-22W
Ness County, Kansas

ELEVATION: 2265'

FORMATION	FROM	TO
Surface soil, shale	0	700
Shale, sand, shale	700	1516
Anhydrite	1516	1550
Shale	1550	2225
Lime and shale	2225	2580
Lime	2580	2870
Lime and shale	2870	4440
Lime	4440	4480

REMARKS

Ran 688' new 24# 8-5/8" surface casing; set and cemented with 350 sacks common cement, 2% gel, 3% C.C. at 693'. Cement circulated. Plug down at 10:15 a.m., December 23, 1980.

Ran 1 electric log

Ran 1 drill stem test.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 780', 25 sacks at 330', hulls and 10 sacks @ 40', 2 sacks in mousehole, 3 sacks in rathole. Plugging completed at 5:45 a.m., December 31, 1980.

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 2nd day of January, 1981.

My appointment expires 3-28-84.

Loneita Barry
Loneita Barry, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1981
CONSERVATION DIVISION
Wichita, Kansas