


15-007-00026-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Barber County, Sec. 31 Twp. 31S Rge. 14W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE - NE - SE  
Lease Owner Sinclair Oil & Gas Company  
Lease Name Mills Estate Well No. 1  
Office Address Box 521, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-28-61 19  
Application for plugging filed 2-28-61 19  
Application for plugging approved 2-28-61 (Verbal) 19  
Plugging commenced 2-28-61 19  
Plugging completed 2-28-61 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well F. W. Hampel  
Producing formation None Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5040 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>None encountered</u>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole mudded from TD 5040' to 260', wooden plug set at 260', 15 sacks cement from 260' to 220', heavy drilling mud from 220' to 35', cement from 35' to surface  
Hole plugged as per Mr. F. W. Hampel, State Inspector's instructions - Job completed at 2:AM2-28-61

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 10 1961  
3-10-61  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Barbour Drlg. Company  
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.  
C. E. Most (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Most  
Box 466, Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March, 19 61

My commission expires 8-13-62 L. B. Reynolds Notary Public.



15-007-00026-0000

MILLS ESTATE NO. 1

SE/4 of Section 31-31S-14W  
Barber County, Kansas  
Sinclair Oil & Gas Company

8-5/8" casing cemented at 310'

Drilling commenced 1-30-61  
Drilling completed 2-27-61

FROM	TO	FORMATION	REMARKS
0'	85'	Red rock & gyp	
85	110	Shale & shells	
110	300	Red bed	
300	550	Red bed & shale	
550	846	Shale & red bed	8-5/8" casing cemented with 250 sacks @ 310'
846	940	Shale	
940	1530	Shale & shells	
1530	1820	Shale & lime	
1820	2005	Shale & lime shells	
2005	2289	Lime	
2289	2925	Lime & shale	
2925	3055	Shale	
3055	3145	Shale & lime streaks	
3145	3220	Shale & lime	
3220	3290	Lime & shale	
3290	3995	Lime	
3995	4035	Lime, shale & sand	
4035	4083	Shale	
4083	4133	Shale & lime	
4133	4612	Lime	
4612	4640	Lime & shale	
4640	4670	Mississippi lime	
4670	4772	Lime	
4772	4785	Lime & chert	
4785	4810	Lime	
4810	4817	Dolomite	
4817	4828	Chert	
4828	4845	Dolomite	
4845	4858	Dolomite & chert	
4858	4925	Sand	
4925	4947	Sand & shale	
4947	4975	Shale	
4975	4996	Arbuckle dolomite	
4996	5040	Arbuckle	Well plugged
T. D.	5040'		

RECEIVED  
STATE CONSERVATION COMMISSION

MAR 29 1961  
3-10-61  
CONSERVATION DIVISION  
Wichita, Kansas

This is a true copy of the driller's log as shown on the drilling tickets.

BARBOUR DRILLING COMPANY

By: *J. M. Barbour Jr*

Subscribed and sworn to before me on this 7th day of March, 1961.

*Merry Jane Burt*  
Notary Public

My commission expires July 27, 1961

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 10 1961  
3-10-61  
CONSERVATION DIVISION  
Wichita, Kansas