

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 30 Twp. SE 31S Rge. (E) 14 (W)

Location as "NE/CNWxSWx" or footage from lines C-NEL/NE1/NE1

Lease Owner H & H Supply Company PMB KCC

Lease Name Glenn B. Oldfather Well No. 2

Office Address P.O. Box 4173, Oklahoma City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_\_\_

Application for plugging filed 11/3/55 19\_\_\_\_

Application for plugging approved 11/4/55 19\_\_\_\_

Plugging commenced 11-16- 1955

Plugging completed 11-20- 1955

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4614 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4614'	3029'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging started 11-16-55 and completed 11-20-55. Measured in to TD 4614'

and dumped in 20' of rocks and 5 sacks of cement. Shot casing off at 3023'

*and pumped in 35 sacks of aqua gel mud*

and pulled pipe out of hole. Plugged well with heavy mud to 300' and set a

permanent rock bridge, and dumped in 25 sacks of cement. Filled hole with heavy

mud to 35' of top and dumped in 15 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. FORBES d/b/a FORBES CASING PULLING CO.

Address P.O. BOX 221, GREAT BEND, KANSAS

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.

Bernard Shanker (~~employee of owner~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

H. & H. SUPPLY CO., Box 4173, Okla City, Okla.


(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1955

11/6/58

My commission expires

Notary Public.



**WELL LOG OF FORMATIONS ENCOUNTERED IN**

**ANDERSON-PRITCHARD OIL CONVECTION**

**WELL NO. 002-110, 2**

**C-12/4 NE/4 NE/4, SEC. 30-31S-14W**

**BLAINE COUNTY, OKLAHOMA**

**RECEIVED**

**OCT 20 1955**

**H. & H. SUPPLY CO.**

FORMATIONS

FROM

TO

Red Rock	0	65
Sand	65	83
Sand, Red Beds & Shells	83	315
Red Beds & Shells	315	450
Red Beds, Shale & Shells	450	825
Red Beds	825	960
Silt & Shale	960	1150
Shale & Red Beds	1150	1220
Shale & Shells	1220	1820
Shale & Silt	1800	1975
Mud	1975	2655
Mud & Shale	2655	2780
Mud	2780	2880
Mud & Shale	2880	2940
Shale	2940	2960
Mud & Shale	2960	3520
Mud	3520	3720
Mud & Shale	3720	3850
Mud	3850	4245
Mud & Shale	4245	4520
Mud	4520	4607
Mud	4607	4612
Mud	4612	4614

Got 2 3/8" ID. 15-5/8" O.D.  
Casing @ 304' and  
Cemented w/ 275 sacks  
Cement.

Please check  
& initial

ES.....

ERS.....

Got 3-1/2" casing @ 4607'  
and cemented w/  
300 sacks cement.

CWD.....

HN.....

Contractor - **Summit Corporation**  
4900 Tower  
Oklahoma City, Okla.

File.....

I hereby certify the foregoing to be a true and correct  
driller's log of the formations encountered in the above well.

*A. Newman*  
A. Newman

Submitted to before me this 15th day of August, 1955.

*Henry J. ...* My Commission Expires *March 1956*  
HENRY J. ...

