

15-007-10208-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 30 Twp. 31S Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines SE/4/ SE/4/ NE/4

Lease Owner H & H Supply Co.

Lease Name Glenn B. Oldfather Well No. 1

Office Address P.O. Box 4173, Oklahoma City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 11/3/55 19

Application for plugging filed 11/3/55 19

Application for plugging approved 11/4/55 19

Plugging commenced 11-10- 19 55

Plugging completed 11-17- 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4630 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4624'	3136'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging started 11-10-55 and completed 11-17-55. Measured in to TD 4630' and dumped in 30' rocks and 5 sacks of cement. Shot casing off at 3107' and pulled casing out of hole. Plugged well with heavy mud, set permanent rock bridge at 300' and dumped in 25 sacks of cement. Filled hole with heavy mud to 35' of top and dumped in 15 sacks of cement for cap on well.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address P. O. Box 221, Great Bend, Kansas

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss. Bernard Shanker

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

H. & H. Supply Co., Box 4173, Okla. City, Okla. (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 1955

My commission expires 11/6/58

Notary Public.

PLUGGING
FILE SEC-30 T 31 R 14 W
BOOK PAGE 13 LINE 36

NOTARY PUBLIC
12-21-55
WICHITA, KANSAS

DETAILED LOG OF FORMATIONS ENCOUNTERED IN

ANDERSON-PRITCHARD OIL WELL

WELL NO. 1

SEC. 30-119-14N

BARREN COUNTY, KANSAS

RECEIVED
OCT 20 1955
H. & H. SUPPLY CO.

FORMATION	FROM	TO
Sand, Rock & Clay	0	800
Red Sand	800	420
Red Rock & Shells	420	800
Red Sand & Sand	800	600
Broken Anhydrite,		
Sand & Red Sand	600	600
Shale & Lime Shells	600	605
Salt & Shells	605	1025
Shale & Shells	1025	1200
Sticky Shale & Shells	1200	1220
Salt & Shale	1220	1340
Shale & Shells	1340	1415
Gyp Lime & Shale	1415	1700
Lime & Shale	1700	2175
Lime	2175	2400
Lime & Shale	2400	3160
Lime	3160	3245
Lime & Shale	3245	3330
Lime	3330	3340
Lime & Shale	3340	3350
Sand & Lime	3350	3380
Sand	3380	4015
Lime	4015	4015
Lime & Shale	4015	4330
Cherty Lime	4330	4335
Lime	4335	4377
Shale & Lime	4377	4622
Lime (Maguelona)	4622	4630

Set 1 1/2" OD casing @ 310 and cemented w/ 300 sacks cement

Set 2 1/2" OD casing @ 4622 and cemented w/ 300 sacks cement

Please r & Initial
BS.....
BNS.....
ERS.....
KCE.....
CWD.....
HN.....
File.....

Total 4630


Contractor - Transit Corporation
1700 Texas
Oklahoma City, Okla.

I hereby certify the foregoing to be a true and correct Driller's log of the formation encountered in the above well.

[Signature]
W. C. Young

Certified to before me this 21st day of July, 1947

[Signature]
Notary Public



ADA
7-28-47