


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barber County, Sec. 30 Twp. 31 Rge. 14 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW SE NE
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Oldfather Well No. 3
Office Address Box 142, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed September 11 1947
Application for plugging filed April 17 1950
Application for plugging approved April 18 1950
Plugging commenced April 24 1950
Plugging completed April 25 1950
Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production September 27, 1949
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Maquoketa Depth to top 4580 Bottom Total Depth of Well 4591 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8	282	none
				5 1/2	4581	2995

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 282'
Set permanent rock bridge in surface pipe.
Dumped 25 sax cement with Bailer.
Filled hole with mud to 15' of top.
Mixed 10 sax of cement for cap on well.

RECEIVED
MAY 10 1950
5-10-50
STATE CORPORATION COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. J. Dearen, o/o Anderson-Prichard Oil Corp.
Address Box 142, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of May, 1950.

Anna M. Laudick
Notary Public.

My commission expires April 26, 1952

22-7377-s

4-49-10M
PLUGGING
FILE SEC 30 T 31 R 14
BOOK PAGE 1 LINE 16

15-667-1021-6000

DRILLERS LOG OF FORMATIONS

ENCOUNTERED IN

ANDERSON-PRICHARD OIL CORPORATION

GLENN B. OLDFATHER WELL NO. 3


C-NW/4 SE/4 ME/4, SEC. 30-31S-14W

BARBER COUNTY, KANSAS

<u>FORMATIONS</u>	<u>FROM</u>	<u>TO</u>	
Red Rock	0	65	
Sand, Red Bed & Shale	65	290	
Red Bed & Shells	290	665	
Anhydrite	665	695	
Red Bed & Shells	695	900	
Shale & Shells	900	1200	
Salt & Shale	1200	1300	
Shale & Shells	1300	1925	
Lime & Shale	1925	2015	
Lime	2015	2605	
Lime & Shale	2605	3380	
Lime	3380	3615	
Lime (Broken)	3615	3715	
Lime	3715	3870	
Shale	3870	3910	
Lime	3910	3960	
Sand & Lime	3960	4014	
Lime	4014	4437	Set 4581' 5-1/2" Casing
Lime & Shale	4437	4580	and cemented w/ 300 Sks.
Dolomite	4580	4583	Cement.
	TD	4583	

Contractor - Transit Corporation
Apco Tower
Oklahoma City, Okla.

I hereby certify the foregoing to be a true and correct driller's log of the formations encountered in the above well.



Walter E. Davis
Assistant Secretary

Certified to before me this 5th day of November, 1947

Perry J. Horne
Notary Public

My Commission Expires

4-78-50
My Commission Expires Mar. 7, 1951

DATE STARTED 8-10-47

COMPLETED 8-31-47