

API NUMBER 15-135-19002-00-00

LEASE NAME Mae Schneider

WELL NUMBER 3

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 12 TWP. 20 RGE. 22 (E) or (W)

COUNTY Ness

Date Well Completed _____

Plugging Commenced 11-21-02

Plugging Completed 11-26-02

RECEIVED
DEC 04 2002

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS POB723, Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-5-02 (date)

by David P. Williams (KCC District Agent's Name).

Is ACC-1 filed? YES If not, is well log attached? _____

Producing Formation Miss Osage Depth to Top _____ Bottom _____ T.O. 4372'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surf. csg.	0	318'	8 3/8		
	Prod. csg.	0	4345	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Rig up Allied - pump 40SK 60/40/6 90 w/ 150# hulls pull + bgs. to 1609' Pump 40SK common w/ 490 c.c. pull 18 3/4" washup let sit 45 min. Pump 120SK 60/40/6 90 lost circ. TOH w/ bgs. let cement sit overnight. Run swab to 500' + T 1/4" w/ 15' its. Rig up to bgs. + circ. cement to surface w/ 35 SK 60/40/6 90 TOH w/ bgs. rig down tie onto 5 1/2" pump 10SK 60/40/6 90 PSI to 500# shut in tie onto 8 3/8" + pump 5SK 60/40/6 90 PSI to 500# + rig down

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address POB723, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: same

STATE OF Kansas COUNTY OF Ellis, ss.

Mark Leifer (Employee of Operator) or (Operator) or

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Mark Leifer

(Address) POB723 Hays, KS

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 2002

Marion Sue Vance
Notary Public

My Commission Expires: 4-30-06



Witnessed by Mike Maier - KCC Dodge City