

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15735790010001

API NUMBER N/A

LEASE NAME May Schneider (SWD)

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

585 Ft. from N Section Line

660 Ft. from W Section Line

SEC. 12 TWP. 20S RGE. 22 (E2 or R2X)

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P.O. Box 5444, Denver, CO 80217

PHONE (303) 298-2696 OPERATORS LICENSE NO. 5208

COUNTY Ness

Date Well Completed 4/64

Character of Well SWD

Plugging Commenced 4/29/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/1/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4385

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	316	
				5 1/2"	4363	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

MIRU Pulled tbg. and pkr. Tally tbg. in hole open ended. Land tbg. @ 3694'. Pump 31 bbl. fresh water followed w/75 sacks 60/40 poz w/10% gel (Halco Lite). Top of cement @ 2810'. Pull tbg. SION Run freepoint, csg. free @ approximately 370'. Cannot justify cost of cut. Perforate squeeze holes @ 900-902 as per SCC's recommendation. Pump 150 sxs 60/40 poz down 5 1/2" csg. Did  
(If additional description is necessary, use BACK of this form.) (over)

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address Ness City, Kansas

STATE OF Colorado COUNTY OF Denver, ss.

J.A. Williams (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.A. Williams for I. E. Dawson

(Address) P.O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 86

Deborah A. Corbett  
Notary Public

My Commission Expires: MY COMMISSION EXPIRES 7/2/90

8-4-86  
AUG 4 1986



not circulate. Try to pump cement down back side. Locked up w/6 sxs in. Pump 144 sxs cement down 5½" casing. 294 sxs cement total. SION Run wire line, tag top of cement @ 587'. Dump 3 yds. Redi-mix down casing, fill to surface. Cut off well head 5' below surface. Fill in all pits, level and clean location. T.D.M.O.

