

15135-205680000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 8 Twp. 20S Rge. 22W ~~XX~~ ~~XX~~
Location as "NE/CNW/SE/SW" or footage from lines SE NW
Lease Owner Kathol Petroleum, Inc.
Lease Name Foss Well No. 1
Office Address 900 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 28, 19 72
Application for plugging filed Verbal Application 19 72
Application for plugging approved Verbal Approval 19
Plugging commenced January 28, 19 72
Plugging completed January 28, 19 72
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4,440 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS					CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	260'	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 4,440 feet (rotary total depth) to 600 feet. Set plug at 600 feet and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 600 feet to 240 feet. Set plug at 240 feet and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 240 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 10 sacks cement, two sacks cement in rathole. Plugging operations accomplished utilizing Allied Oilwell Cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1972
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas 67202
(If additional description is necessary, use BACK of this sheet)

STATE OF Kansas, COUNTY OF Sedgwick
Dean Britting, Agent
I, Dean Britting, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Dean Britting
200 North Main, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 2nd day of February, 19 72
Elsie Willison
Notary Public.
My commission expires June 30, 1974

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-135-20568-0000

COMPANY Kathol Petroleum, Inc.

SEC. 8 T. 20S R. 22W
LOC. SE NW

FARM FOSS

NO. 1

TOTAL DEPTH 4,440'

COMM. January 19, 1972

COMP. January 28, 1972


SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED

COUNTY Ness

KANSAS



CASING

20

10

15

12

13

8

6

5

5/8" 260' cemented w/180 sxs cement ELEVATION 2223 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay and Shale	200'
Blue Shale	261'
Shale and Red Bed	812'
Anhydrite	821'
Shale	905'
Sand and Shale	1,447'
Anhydrite	1,490'
Shale	1,585'
Shale and Shells	2,222'
Lime and Shale	3,035'
Shale and Lime	3,235'
Lime and Shale	3,452'
Lime	3,595'
Lime and Shale	4,005'
Lime	4,440'
Rotary Total Depth	4,440'

I hereby certify the above and foregoing
to be a true and correct log of the above
described well as shown by the drilling
reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas

County of Sedgwick

SS:

Subscribed and Sworn to before me a Notary
Public in and for said county and state
this 2nd. day of February, 1972.

Elsie Willison
Elsie Willison-Notary Public

Commission Expires:

June 30, 1974



RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1972
CONSERVATION DIVISION
Wichita, Kansas